

**ANNUAL INTEGRATED RESOURCE PLAN PROGRESS REPORT AND FIVE-YEAR
PLAN FOR DEPARTMENT OF ENERGY INSTALLATIONS HAVING ALLOCATIONS
OF POWER FROM THE WESTERN AREA POWER ADMINISTRATION**

**PREPARED FOR
U.S. DEPARTMENT OF ENERGY
FEDERAL ENERGY MANAGEMENT PROGRAM**

UNDER CONTRACT NO. DE-AC01-07EE11509

TASK ASSIGNMENT NO. 3

JULY 2008

PREPARED BY

EXETER

ASSOCIATES, INC.

5565 Sterrett Place

Suite 310

Columbia, Maryland 21044

TABLE OF CONTENTS

	<u>Page</u>
SECTION 1 - INTRODUCTION	
1. Purpose.....	1-1
2. Report Organization.....	1-2
3. Responsible Parties.....	1-2
SECTION 2 - JOINT POWER SUPPLY ARRANGEMENTS FOR THE DOE'S NORTHERN CALIFORNIA LABORATORIES	
1. Introduction.....	2-1
2. Actual and Projected Energy and Coincident Demands.....	2-2
3. Current and Projected Supply-Side Power Supply Resources.....	2-5
SECTION 3 - LAWRENCE BERKELEY NATIONAL LABORATORY	
1. Introduction.....	3-1
2. Actual and Forecast Demands and Energy.....	3-2
3. Current DSM / Conservation Efforts.....	3-5
4. New Projects	3-8
SECTION 4 - LAWRENCE LIVERMORE NATIONAL LABORATORY	
1. Introduction.....	4-1
2. Actual and Forecast Demands and Energy.....	4-2
3. Current DSM Projects.....	4-5
4. Livermore Energy Savings Goals.....	4-7
5. New Projects	4-10
6. Impact of Conservation and Other Demand-Side Programs	4-12
SECTION 5 - SITE 300	
1. Introduction.....	5-1
2. Actual and Forecast Demands and Energy.....	5-2
3. Current DSM Projects.....	5-5
4. New Projects	5-6
5. Impact of Demand-Side Program.....	5-6
SECTION 6 - STANFORD LINEAR ACCELERATOR CENTER	
1. Introduction.....	6-1
2. Actual and Forecast Demands and Energy.....	6-2
3. Current DSM Energy Efficiency and Renewable Resource Projects.....	6-5
4. Current Laboratory Goals and EO 13123 Impacts	6-8
5. Projected DSM / Energy Efficiency / Renewable Resource Projects.....	6-9
ATTACHMENT TO SECTION 6	
SECTION 7 - NEVADA TEST SITE	
1. Introduction.....	7-1
2. Projected Demands and Energy	7-1
3. Current Demand-Side Programs.....	7-2
4. Projected DSM/Energy Efficiency Projects.....	7-3
5. Energy Goals.....	7-4

SECTION 1
INTRODUCTION

1. Purpose

On August 16, 1994, the Western Area Power Administration (Western) proposed the Energy Planning and Management Program, requiring nearly all of its customers to prepare Integrated Resource Plans (IRPs). The Program's primary goal is to improve the planning and efficiency of energy use by Western's customers. On October 20, 1995, Western issued its *Final Rule* in the *Federal Register*, which detailed the requirements for IRP submissions to Western.¹ This Progress Report submission, made by the U.S. Department of Energy (DOE) on behalf of the DOE installations receiving Western power allocations, fulfills Western's Annual IRP Progress Report requirements as implemented and set forth in Western's *Final Rule*. The DOE installations represented in this joint submission are: Lawrence Berkeley National Laboratory (LBNL), Lawrence Livermore National Laboratory (LLNL), the LLNL Site 300 installation (Site 300), the Stanford Linear Accelerator Center (SLAC), and the Nevada Test Site (NTS).

In addition to fulfilling Western's Annual IRP Progress Report requirements, the updates prepared for Western will assist in guiding the DOE installations represented in this report to meet their obligations to lower energy usage pursuant to Executive Order 13123 (EO 13123) and the Energy Policy Act of 2005, which require significant decreases in energy usage by federal government agencies. Required reductions in energy usage for DOE facilities were codified further by DOE Order O 430.2B, approved February 27, 2008. Integrated resource planning provides a framework within which customers can plan and implement the least-cost approach to meet power requirements by addressing both supply-side and demand-side resources. This approach serves to accommodate compliance with federal energy usage requirements, and also serves to assist Western in obtaining the information and projections needed for its own planning.

¹ U.S. Department of Energy, Western Area Power Administration, Final Rule, Title 10, Part 905, Federal Register Notice, October 20, 1995 (revised in the Code of Federal Regulations January 1, 1999, and May 1, 2000).

This report combines the studies Western requires of DOE facilities having entitlements to Western preference power. First, each facility must update previous IRP studies submitted to Western in previous years. The purpose of such updates is to apprise Western of progress made over the previous year and indicate any change in planning that would have a significant impact upon energy usage. Second, Western asks each DOE facility to submit a forward-looking IRP study showing how it plans to utilize supply- and demand-side resources to meet its requirements in the future extending for a minimum of five years, covering the period 2009-2013.0

2. Report Organization

This report is divided into seven sections, including this introduction. All of the DOE installations included in this update operate under similar procedural guidelines and are subject to the same set of legislative and regulatory requirements regarding energy conservation and the acquisition of utility services, have access to the same funding sources, and adhere to the same operational guidelines. Section 2 discusses changes in the joint power supply arrangements for the DOE's Northern California laboratories (LBNL, LLNL, Site 300, and SLAC) and describes their current and future supply-side arrangements. Sections 3 through 7 present updated information on an installation-by-installation basis for all the DOE installations receiving Western power allocations. Each section of the report deals with the requirements of the Annual IRP Progress Report, as well as addressing the requirements of the forward-looking IRP.

3. Responsible Parties


The responsible party for this report is:

Mr. David McAndrew
U. S. Department of Energy
Office of Federal Energy Management Program
1000 Independence Avenue, S. W.
Washington, D. C. 20585

Telephone: (202) 586-7722

4. Approval

I approve the preparation of DOE's IRP Progress Report and Five-Year Plan and its submission to Western.

A handwritten signature in dark ink, appearing to read 'D. McAndrew', is written over a horizontal line.

David McAndrew
U. S. Department of Energy
Office of Federal Energy Management Program
1000 Independence Avenue, S. W.
Washington, D. C. 20585

Telephone: (202) 586-7722

SECTION 2

JOINT POWER SUPPLY ARRANGEMENTS FOR THE DOE'S NORTHERN CALIFORNIA LABORATORIES

1. Introduction

The U. S. Department of Energy continues to plan electric power supply arrangements for LBNL, LLNL, Site 300, and SLAC so as to minimize the combined costs of the four laboratories. (Collectively, the four laboratories are referred to as the DOE's Northern California Laboratories, or the Consortium.) The DOE Office of Science, Berkeley Site Office (DOE/BSO) then re-bills each of the laboratories to accomplish three objectives: (1) recover the total cost of power; (2) allocate these power costs among the four laboratories in a fair and equitable manner; and (3) provide prices to the laboratories that, to the extent practicable, reflect the appropriate marginal costs of capacity and energy to provide the proper price signals for decisions regarding energy conservation and demand-side management.

Effective January 1, 2005, DOE/BSO entered into an Interconnection Agreement with Pacific Gas and Electric Company (PG&E) and several new exhibits to its Intra-Agency Agreement No. 90-SAO-00001 with Western which, together, conferred on the four laboratory sites comprising the Consortium, wholesale status in the bulk power electric market. As such, Western purchases power in the wholesale market on behalf of the Consortium and meets the main load of the four laboratories on a real-time, scheduled, conjunctive basis. Western operates as DOE/BSO's portfolio manager and scheduling coordinator for those loads located in the control area of the California Independent System Operator (CAISO).

The laboratories no longer have independent contract rates of delivery of Central Valley Project (CVP) power. Rather, the Consortium has a 4.5 percent share of the marketed CVP energy. That CVP energy is combined with block power purchases at the California-Oregon border or in Northern California (NP15), and with day-ahead purchases and sales of excess energy in order to match the Consortium's loads with its resources. Western combines most of the appropriate charges (CVP power, other third-party power, and day-ahead purchases) and provides DOE/BSO with one consolidated

bill. It is these consolidated costs that are recovered through DOE/BSO's rebilling rates to each of the laboratories.

2. Actual and Projected Energy and Coincident Demands.

Table 2-1 presents actual energy and coincident demand data for the combined loads of the four laboratories comprising the Consortium, which cover the period 2003 through April 2008. Data presented for the May – December 2008 period are estimated. Table 2-2 shows projected energy and coincident demand data for the Consortium.

Table 2-1

**U. S. Department of Energy
Northern California Consortium
Actual Energy and Demand
2004 – 2008
Energy (mWh)**

Month	2004	2005	2006	2007	2008*
January	68,089	48,715	74,117	68,234	82,003
February	67,882	45,197	69,058	70,850	79,150
March	74,393	54,788	76,299	79,748	83,001
April	72,202	67,671	77,464	75,614	60,871
May	74,742	69,857	77,567	72,493	61,309
June	74,135	74,404	80,552	81,443	60,805
July	78,997	80,674	85,073	87,510	63,749
August	47,021	78,905	67,886	86,133	62,180
September	49,117	77,457	47,238	52,312	56,947
October	52,911	61,937	49,475	52,810	58,959
November	46,558	66,126	49,847	53,534	57,431
December	47,774	78,280	52,566	72,597	57,009
Total	753,821	804,012	807,141	853,277	783,416

Coincident Demand (kW)

Month	2004	2005	2006	2007	2008*
January	106,590	73,761	114,825	111,081	123,183
February	109,950	75,366	117,702	121,419	123,324
March	115,674	94,014	117,045	123,915	121,557
April	118,029	109,704	125,907	121,713	126,990
May	119,520	118,098	126,219	123,429	96,607
June	118,626	124,302	132,045	135,072	101,086
July	125,016	127,224	134,067	135,495	101,785
August	81,156	127,425	129,693	133,941	100,689
September	84,900	127,461	82,947	119,499	93,189
October	94,944	125,829	82,947	95,451	94,636
November	73,119	115,053	78,921	85,737	95,999
December	73,512	117,891	81,096	114,222	92,158
Total	1,221,036	1,336,128	1,323,414	1,420,974	1,271,203
Maximum	125,016	127,461	134,067	135,495	126,990

* January to April data are actual. May to December data are estimated.

Table 2-2
U. S. Department of Energy
Northern California Consortium
Energy and Demand Projections
2009 - 2013
Energy (mWh)

Month	2009	2010	2011	2012	2013
January	62,092	66,487	75,600	82,883	83,098
February	58,361	62,844	71,959	78,561	78,752
March	60,652	65,518	82,079	83,002	83,203
April	61,865	68,585	79,679	80,437	80,633
May	64,875	71,842	78,369	79,385	79,745
June	64,246	66,086	77,378	78,321	78,672
July	67,341	69,233	81,003	82,097	82,462
August	58,371	60,162	72,012	73,033	73,399
September	56,598	58,248	69,770	70,734	71,088
October	67,819	70,115	82,149	83,010	83,381
November	63,407	65,746	77,348	78,192	78,547
December	60,413	67,626	74,606	75,433	75,770
Total	746,042	792,494	921,954	945,090	948,752

Coincident Demand (kW)

Month	2009	2010	2011	2012	2013
January	92,406	101,118	116,912	128,250	128,540
February	94,016	102,702	118,497	129,834	130,125
March	96,831	105,561	130,561	132,790	133,080
April	101,555	113,290	129,957	131,216	131,507
May	104,370	115,815	124,439	126,668	127,346
June	109,418	112,904	130,152	132,090	132,769
July	110,113	113,789	131,231	132,879	133,460
August	95,221	99,347	117,080	118,824	119,502
September	94,437	98,301	116,325	117,778	118,457
October	108,910	112,718	131,032	132,195	132,873
November	105,160	109,184	127,402	128,564	129,243
December	100,911	111,796	122,842	124,005	124,683
Total	1,213,346	1,296,526	1,496,430	1,535,093	1,541,586
Maximum	110,113	115,815	131,231	132,879	133,460

3. Current and Projected Supply-Side Power Supply Resources.

During 2008, the Consortium contracted for 75 MW from the Pacific Northwest with power delivered at the California Oregon Border (COB). That power is then delivered to Western's Tracy Substation, where it is delivered to each of the laboratories over the transmission grid under the control of the California Independent System Operator (ISO), or to Livermore over Western's Tracy tie-line. In addition, during 2008, the Consortium purchased an additional 25 MW during the first quarter of the year in Northern California (referred to as NP15) and an additional 10 MW in April 2008. Because unexpected budgetary cutbacks forced the early termination of a major experiment at the Stanford Linear Accelerator Center (SLAC), the Consortium also sold 35 MW of power that was excess to their needs during the second and third quarters of 2008.

During 2009, the Consortium has contracted for the delivery of 50 MW at COB and is considering the extent to which additional purchases must be made to meet its energy and demand requirements. The Consortium has also purchased 25 MW at COB to meet a portion of their needs for 2010. The Consortium has adopted a risk management protocol to determine how it can best minimize the impact on supply-side resource costs of the volatility of market. Beyond this, the Consortium purchased 26,500 mWh of renewable energy certificates (RECs). Purchases of additional RECs may be required in the future. As some of the details set out in the sections of individual laboratories shows, the laboratories are considering and evaluating other renewable energy resources as well.

Table 2-3 summarizes the Consortium's risk management and procurement strategy for the next several years.

Table 2-3

Summary of the Consortium's
Risk Management and Procurement Strategy

- Purchase substantially all of the Consortium's projected energy requirements for the first two forward years with fixed price forward purchases
 - Minimizes the Consortium's exposure to price volatility and maximizes the predictability of costs for two years forward
- Utilize the Consortium's transmission entitlement to buy relatively lower cost energy at COB
- Gradually reduce the level of fixed price forward purchases in years three and four; to illustrate
 - 2008: 75 MW at COB; various NP-15 purchases; CVP energy
 - 2009: 75 MW at COB; various NP-15 purchases; CVP energy
 - 2010: 50 MW at COB; CVP energy
 - 2011: 25 MW at COB; CVP energy
 - 2012: CVP energy

SECTION 3
LAWRENCE BERKELEY NATIONAL LABORATORY

1. Introduction

During FY2007 and for the next several years, the Lawrence Berkeley National Laboratory (LBNL) receives all of its electricity from the Western Area Power Administration (Western). Some of this electricity is from a share of the Consortium's entitlement to Central Valley Project (CVP) power marketed by Western. The balance of LBNL's resources is from a share of third party contracts Western secured acting as an agent for the Consortium. Electricity is delivered to LBNL over the high-voltage transmission grid under the control of the California Independent System Operator (ISO). Separately, Pacific Gas and Electric Company (PG&E) supplies electricity to a number of leased spaces on the site. This report focuses upon current and future demand-side activities at LBNL to fulfill the requirements necessary for the laboratory to continue receiving Western power.

The balance of this section is organized as follows. Subsection 2 below presents actual and projected demand and energy data for LBNL. Subsection 3 shows actual demand-side management (DSM) and conservation projects undertaken by LBNL during the past several years, identifies the reduction in energy intensity, energy and cost savings arising from such projects pursuant to DOE directives. Subsection 4 identifies DSM and other energy conservation projects under consideration that are to be implemented over the next few years and identifies the energy savings resulting from such projects.

Table 3-1 summarizes LBNL's energy usage and peak demand during the FY2003 – FY2007 period. In addition, Table 3-1 shows the laboratory's cost of electricity during this time period.

Table 3-1

LAWRENCE BERKELEY NATIONAL LABORATORY
Berkeley, California

<u>Data Summary</u>	<u>FY 2003</u>	<u>FY 2004</u>	<u>FY 2005</u>	<u>FY 2006</u>	<u>FY 2007</u>
Building Energy (mWh) (1)	64,334	78,077	70,537	60,615	60,176
Excluded Energy (mWh) (2)	25,031	14,619	16,725	34,331	41,913
Renewable Energy Credits (RECs) (3)	0	0	2,374	2,848	3,157
Peak Demand (kW)	12,312	11,304	11,232	11,159	11,961
Electricity Expenditures (\$K)	\$5,116	\$6,189	\$7,817	\$9,424	\$10,554
1. Corrections were made to some of the previously reported values. 2. Process energy use exclusions from energy intensity reduction goal reporting are provided above. Previous IRP Reports have not listed this "excluded" energy use. 3. LBNL and other San Francisco Bay Area DOE facilities entered into an agreement to purchase RECs from WAPA. RECs are subtracted from building energy use to help reduce energy use intensity towards reduction goals. The agreement to purchase RECs expires at the end of 2010. RECs are being phased out for the purpose of reducing energy use intensity, scheduled at 20% each year, starting in FY 2008, until exhausted. REC purchases may still be used to satisfy renewable energy goals.					

2. Actual and Forecast Demands and Energy

Table 3-2 shows LBNL's actual demand and energy during the period 2004 – April 2008. (Estimated demand and energy data are included for the May – December 2008 period.) Table 3-3 shows LBNL's projected demand and energy during the 2009 – 2013 period.

Table 3-2

**U. S. Department of Energy
Northern California Consortium
Lawrence Berkeley National Laboratory
Actual Energy and Demand
2004 - 2008**

Energy (mWh)

Month	2004	2005	2006	2007	2008*
January	5,579	5,845	5,993	6,442	6,467
February	5,742	5,676	5,933	5,748	6,301
March	6,487	6,414	6,723	6,524	6,706
April	5,935	5,338	6,479	6,391	6,198
May	4,886	5,878	6,492	5,971	6,301
June	6,148	6,263	6,585	6,126	5,894
July	6,355	6,412	6,848	6,488	6,606
August	6,148	6,265	6,375	7,026	6,686
September	6,263	6,170	6,374	6,567	5,901
October	6,398	6,358	6,044	6,863	7,188
November	5,896	5,990	5,216	6,426	6,043
December	5,828	5,780	5,395	6,072	3,884
Total	71,666	72,388	74,456	76,645	74,175

Demand (kW)

Month	2004	2005	2006	2007	2008*
January	11,232	10,440	10,584	10,620	10,908
February	10,296	10,872	10,764	10,656	10,944
March	11,376	11,016	10,620	10,908	10,980
April	10,656	10,188	11,088	11,196	10,584
May	9,144	10,908	11,196	11,232	11,600
June	10,656	10,728	12,600	11,448	11,600
July	11,304	11,232	12,456	11,628	11,600
August	11,232	11,160	11,556	12,168	11,700
September	11,520	11,484	11,340	11,808	11,800
October	11,664	11,016	10,836	11,916	11,700
November	10,512	10,764	9,719	11,124	11,800
December	10,512	10,440	9,864	11,016	11,700
Total	130,104	130,248	132,623	135,720	136,916
Maximum	11,664	11,484	12,600	12,168	11,800

* January – April are actual data; May – December are projected.

Table 3-3

**U. S. Department of Energy
Northern California Consortium
Lawrence Berkeley National Laboratory
Energy and Demand Projections
2009 - 2013
Energy (mWh)**

Month	2009	2010	2011	2012	2013
January	7,870	8,893	14,006	21,289	21,504
February	6,701	7,623	12,238	18,840	19,031
March	6,511	7,506	18,967	19,890	20,091
April	6,574	7,537	18,631	19,389	19,585
May	7,094	8,084	19,711	20,727	21,087
June	6,658	7,617	18,909	19,852	20,203
July	7,403	8,397	20,167	21,261	21,626
August	7,484	8,478	20,328	21,349	21,715
September	6,666	7,625	19,147	20,111	20,465
October	8,072	8,992	21,026	21,887	22,258
November	6,890	7,771	19,373	20,217	20,572
December	4,726	10,635	17,615	18,442	18,779
Total	82,649	99,158	220,118	243,254	246,916

Demand (kW)

Month	2009	2010	2011	2012	2013
January	13,000	15,000	22,700	34,400	34,700
February	13,100	15,000	22,700	34,400	34,700
March	13,100	15,000	32,200	34,500	34,800
April	13,200	15,000	32,200	33,500	33,800
May	13,300	15,000	32,500	34,800	35,500
June	13,300	15,000	32,800	34,800	35,500
July	13,300	15,000	33,000	34,700	35,300
August	13,400	15,100	33,400	35,200	35,900
September	13,500	15,200	33,800	35,300	36,000
October	13,500	15,100	34,000	35,200	35,900
November	13,600	15,200	34,000	35,200	35,900
December	13,500	22,600	34,000	35,200	35,900
Total	159,800	188,200	377,300	417,200	423,900
Maximum	13,600	22,600	34,000	35,300	36,000

3. Current DSM / Conservation Efforts

In the 1999 Integrated Resource Plan (IRP), the LBNL set goals to meet the updated requirements of Executive Order 13123 (issued June 1999); reduction in the site's total energy usage per square foot by 20 percent by FY 2005 and 25 percent by FY 2010, relative to a FY 1990 baseline. The laboratory achieved these goals through the energy efficiency measures and retrofit projects that were completed by FY 1999.

The 1999 energy reduction goals were recently superseded and updated by the Energy Policy Act of 2005 (August 8, 2005), Executive Order 13423 (January 26, 2007), and the Energy Independence and Security Act of 2007 (December 19, 2007), culminating with signing of the updated Department of Energy Order 430.2B Departmental Energy, Renewable Energy and Transportation Management on January 27, 2008. Energy usage intensity reduction goals have been increased to 3 percent per year, starting in FY 2006, for a total 30 percent reduction by the end of FY 2015, with a revised baseline of FY 2003.

Table 3-4 summarizes total annual energy consumption, by type, renewable energy credit (REC) purchases, building floor areas and a comparison of energy use intensity savings achieved to the goals. This table includes all LBNL energy usage and building areas. The results in Table 3-4 show that LBNL had reduced energy use intensity by over 8 percent at the end of FY 2007 from the updated FY 2003 baseline. To achieve these savings, LBNL implemented the energy efficiency projects listed on Table 3-5, below. Planning to achieve the FY 2015 goal involves implementation of an energy savings performance Contract (ESPC), which is currently under development.

Table 3-4

**LBNL Performance towards DOE O 430.2B
Energy Use Intensity Reduction Goals**

Data Summary		FY 2003	FY 2004	FY 2005	FY 2006	FY 2007
Buildings Power Use	(mWh)	64,334	78,077	70,537	60,615	60,176
RECs	(mWh) ⁽¹⁾	0	0	2,374	2,848	3,157
Buildings Nat Gas Use	(MCF)	161,193	156,171	146,760	150,933	148,710
Building Energy Use	(B BTU) ⁽²⁾	385,698	427,411	383,822	352,713	350,025
Buildings Floor Area	(K-GSF)	2,046	1,972	2,036	2,096	2,020
Excluded Floor Area	(K-GSF) ⁽³⁾	43	41	41	284	41
Total Floor Area	(K-GSF)	2,089	2,013	2,077	2,380	2,061
Excluded Power Use	(mWh) ⁽³⁾	25,031	14,619	16,725	34,331	41,913
Total Electric Power	(mWh)	89,366	92,697	87,262	94,947	102,089
Energy Use Intensity	(K-BTU / GSF)	188.528	216.700	188.493	168.259	173.283
Savings from FY 2003 Baseline		N/A	(14.9%)	0.02%	10.75%	8.1%
DOE O 430.2B Savings Goals ⁽⁴⁾		N/A	N/A	N/A	3.0%	6.0%

Notes:

1. LBNL and other San Francisco Bay Area DOE facilities entered into an agreement to purchase Renewable Energy Credits (RECs) from WAPA. RECs are subtracted from building energy use to help reduce energy use intensity towards reduction goals. RECs are being phased out for the purpose of reducing energy use intensity, scheduled at 20% each year, starting in FY 2008, until exhausted. REC purchases may still be used to satisfy site renewable energy goals.
2. Total energy use is determined by converting electric power and natural gas to the common units per conversion factors: 3,412 BTU/kWh and 1,031 BTU/CF, respectively.
Criteria allow process energy uses and building areas to be excluded from energy use intensity savings determinations. Such uses are defined as energy-intensive loads driven by mission and/or operational requirements that are not influenced by conventional building energy conservation measures. Annual self-certification is required.
3. Energy use intensity savings goals of DOE O 430.2B originated in EO 13423 and require savings of 3% per year, starting in FY 2006 to achieve a total savings of 30% by the end of FY 2015. FY 2003 has been established as the "Baseline" year.

TABLE 3-5

LAWRENCE BERKELEY NATIONAL LABORATORY
FY 1997 THROUGH 2007 PROJECT SUMMARY DATA

<u>Project</u>	<u>Completion Date</u>	<u>Cost (\$, 000)</u>	<u>Annual Savings⁽¹⁾ (mWh)</u>	<u>(\$, 000)</u>
Motor Replacements	Dec. 1996	507	120	7.4
Group II EMCS Upgrade	Mar. 1997	1,100	2,270	140.4
Energy Upgrades – Bldgs. 54, 72, & 76	Jul. 1997	912	185	11.4
Bldg. 62 Retrofits	Sep. 1997	342	440	27.2
Total FY 1997		\$2,861	3,015	\$186.4
Packaged HVAC	Dec. 1997	211	450	27.8
Bldg. 6 Lighting Upgrade	Jul. 1998	75	200	12.4
Process Loads	Jul. 1998	226	565	34.9
Small Fan Control	Aug. 1998	116	111	6.9
New Lighting Technologies	Aug. 1998	160	530	32.8
Total FY 1998		\$788	1,856	\$114.8
<u>Project</u>	<u>Completion Date</u>	<u>Cost (\$, 000)</u>	<u>Annual Savings⁽¹⁾ (mWh)</u>	<u>(\$, 000)</u>
Bldg. 2 Chiller Turbomodulator	Jul. 1999	75	200	12.4
Cooling Towers	Sep. 1999	209	580	35.9
Bldg. 70 HVAC Zone Controls	Sep. 1999	50	165	10.2
Bldg. 34 Chiller & Cooling Tower	Sep. 1999	750	400	24.7
Total FY 1999		\$1,084	1,345	\$83.2
		(\$, 000)	(mWh)	(\$, 000)
Sealing Ductwork – Bldg 90	July 2004	60	210	13.0
Total FY 2004		\$60	210	\$13.0
Total FY 2005	No projects were completed during this year			
Total FY 2006	No projects were completed during this year			
Sealing Ductwork - Bldgs 50 & 70	June 2007	96 ⁽²⁾	227	14.0
Retro Commission B66 3 rd Floor	Aug. 2007	265 ⁽²⁾	810	50.1
Total FY 2007		\$541	1,210	\$64.1
Total for FY 1997 through 2007		\$5,334	7,636	\$461.5

Notes:

1. Annual cost savings are based on an updated Western rate of \$61.84 per mWh.
2. Project costs from records of project completion.

The laboratory's prior IRP's included action plans to implement energy conservation and DSM measures to reduce LBNL's energy requirements. The short-term and long-term plans that were completed by FY 2007 have collectively provided annual savings of 7,636 mWh of electricity and about \$461,500. All of the DSM and energy efficiency projects, shown on Table 3-4, implemented since FY 1997, are still in operation today; annual energy savings have continued at the previously stated rates for these projects.

Renewable Energy. To date, LBNL has satisfied the renewable energy acquisition goal by purchasing RECs arranged by Western. Western has purchased a total of 26,500 mWh of RECs per year through FY 2010 for the Consortium at a cost of \$1.00 per mWh. The RECs are distributed to assure that each of the laboratories achieves the 3 percent renewable energy goal.

4. New Projects

An ESPC project is currently being developed with NORESO under DOE's Super-ESPC program to identify, develop and install measures that will provide compliance with the 30 percent energy use intensity savings goal by the end of FY 2015. Project costs, energy and other related cost savings are summarized on Table 3-6, based on NORESO's Initial Proposal (IP), submitted, as revised, in November 2007. A detailed energy study is currently underway which will result in submittal of a delivery order proposal scheduled for September 2008. Contract signing is expected in January or February 2009.

TABLE 3-6

**LAWRENCE BERKELEY NATIONAL LABORATORY
NEW PROJECTS⁽¹⁾**

<u>Project</u>	<u>Construction Completion</u>	<u>Implementation</u>	<u>Annual Energy & Cost Savings⁽³⁾</u>			
		<u>Price⁽²⁾</u> (\$, 000)	<u>Power</u> (mWh)	<u>NG</u> (MCF)	<u>O&M</u>	<u>Total</u> (B BTU)
ESPC Project	FY 2011	\$11,295	8,258 \$685K	53,008 \$476K	- \$76K	82.84 \$1,236K
The ESPC Project IP includes the following Energy Conservation Measures (ECMs):						
ECM-1	Controls / R-Cx	\$7,938	4,427	42,866	\$53K	57.98
ECM-2	Duct Sealing	\$1,104	1,373	4,846	-	9.53
ECM-3	Fume Hood Tune	\$1,667	1,628	6,940	-	12.49
ECM-16	Lighting	\$92	830	0	\$23K	2.83

Notes:

1. All the above data are estimates from the IP. DES activities are currently underway; it is expected that additional ECMs will be developed and proposed.
2. Implementation Price is the ESPC construction cost, before finance charges.
3. Total energy use is determined by converting electric power and natural gas to the common units per conversion factors: 3,412 BTU/kWh & 1,031 BTU/CF, respectively.

Renewable Energy. LBNL has evaluated renewable energy applications on several occasions over the past years and has not been able to demonstrate a life-cycle cost-effective project. The feasibility of installing on-site renewable energy is being reinvestigated presently, with the assistance of a consultant retained by the DOE's Transformational Energy Action Management (TEAM) Initiative. TEAM consultant findings are expected to be available in early June 2008. Preliminary indications are that there may be a couple feasible projects, particularly a solar hot water system at the cafeteria and a PV installation mounted on the existing racks on the Building 90 roof.

Implementation of these measures will not achieve compliance with the renewable energy percentage goals. Additional renewable energy will be secured, as needed, either by direct purchase of renewable power and/or via the purchase of additional RECs.

Another possibility of achieving the renewable energy goals for all three SF Bay-Area DOE facilities is to locate a large PV system at the LLNL site, with participation from LBNL and SLAC. Execution of this effort could provide a PV installation with generating capacity of 15 to 30-MW. Several hurdles would have to be overcome to implement a joint project of this nature. The first would require DOE to accept a joint project at one of the laboratories with the other two laboratories also receiving credit for on-site renewable power generation. Next, the laboratories would have to reach a collaborative agreement to share construction support costs. Most important, the economics of the proposed installation would have to improve significantly from the current tentative 19-year simple payback period determined by the TEAM consultant.

Measurement Strategies. Almost all LBNL buildings are metered for electric power and natural gas consumption. In many cases, sub-meters are installed to measure the energy consumption and demand of specific processes. Metered energy consumption is, thus, used to verify savings of individual measures. Trend data from

newly installed heating, ventilation and air-conditioning (HVAC) direct digital controls (DDC) will be used to measure and verify energy savings from any ESPC project.

Impact of Projected Electric Energy Conservation Measures. Projections of LBNL on-site electric energy consumption through FY 2014 are provided on Table 3-7. This shows the impact of conservation measures currently planned under the ESPC in Table 3-6. No ESPC demand savings are currently projected.

Other Energy Efficiency Measures and Policies at LBNL. DOE uses employee incentive programs to recognize outstanding contributions toward energy and dollar savings at DOE facilities and field organizations. Awards are presented to recognize outstanding contributions toward increased energy efficiency within the DOE complex, and draw attention to energy efficiency efforts, as mandated by the Energy Policy Act of 2005, Executive Order 13423 and by DOE O 430.2B.

TABLE 3-7 LAWRENCE BERKELEY NATIONAL LABORATORY ENERGY PROJECTIONS (WESTERN POWER) (mWh)			
<u>Federal Fiscal Year</u>	<u>Base Case Energy Projections</u>	<u>Cumulative Estimated Savings⁽²⁾</u>	<u>Net Energy Requirements⁽³⁾</u>
2003 ⁽¹⁾	74,400	Included	74,400
2007 ⁽¹⁾	69,500	Included	69,500
2008	73,000	0	73,000
2009	80,987	365	80,622
2010	95,800	4,352	91,448
2011	197,541	8,039	189,502
2012	248,980	8,258	240,722
2013	254,110	8,258	245,852
2014	255,174	8,258	246,916
Notes: 1. FY 2003 & FY 2007 values are actual, including the effects of previously implemented energy savings projects. 2. The only future energy savings effort planned at this time is the Energy Savings Performance Contract. (Refer to Table 3-5.) Savings are indicated based on the revised ESPC Initial Proposal dated 14-Nov-2007. The final project, when implemented is expected to include additional measures, increasing the savings. 3. This summary does not include off-site facilities which receive power from PG&E.			

SECTION 4

LAWRENCE LIVERMORE NATIONAL LABORATORY

1. Introduction

The Lawrence Livermore National Laboratory (LLNL) is a renowned applied science facility that is part of the National Nuclear Security Administration (NNSA) within the Department of Energy. Located near Livermore, California, as a national security laboratory, LLNL is responsible for ensuring that the nation's nuclear weapons remain safe, secure, and reliable through the application of advances in science and engineering.

LLNL receives all of its electricity under arrangements between DOE's Berkeley Site Office and Western. A portion of this power is from the Consortium's entitlement to CVP power marketed by Western. The balance of LLNL's resources is from a share of third party contracts Western secured acting as an agent for the Consortium. Power is delivered to LLNL over a Western-owned 230 kilovolt transmission line between Western's Tracy Substation and the Livermore Substation. This section of the report focuses on LLNL's demand-side activities, since supply-side resources are secured under the auspices of the Berkeley Site Office acting on behalf of all of DOE's Northern California Laboratories. We also discuss LLNL's work in securing renewable resources to meet its future requirements.

Table 4-1 summarizes Livermore's demand and energy usage during the FY 2005 – FY 2008 period. Estimated expenditures of electricity are also presented.

<p align="center">Table 4-1</p> <p align="center">Lawrence Livermore National Laboratory</p> <p align="center">Livermore, California</p>			
Data Summary	FY 2005	FY 2007	FY 2008
Total Energy (mWh)*	337,421	379,228	383,264
Peak Demand (kW)	60,660	63,180	60,912
Electricity Expenditures	\$16,104,614	\$18,075,963	\$20,132,608
<p>* LLNL Total Energy (mWh) data is limited to electric power provided by Western for the federal fiscal years, commencing in October, each year.</p>			

The remainder of this section is organized as follows: Section 2 presents actual (2004 – April 2008) and forecasted (May 2008 – 2013) demand and energy data. Section 3 reports the results of current demand-side conservation and energy efficiency measures in place at LLNL and their impact on energy and power cost. Section 4 identifies demand-side measures to be considered to comply with DOE’s requirements for reductions in energy usage in the future.

2. Actual and Forecast Demands and Energy

Table 4-2 shows LLNL’s actual demand and energy during the period 2004 – April 2008. (Demand and energy data for the May – December 2008 period are estimated.) Table 4-3 shows LLNL’s projected demand and energy during the 2009 – 2013 period.

Table 4-2
U. S. Department of Energy
Northern California Consortium
Lawrence Livermore National Laboratory
Actual Energy and Demand
2004 - 2008
Energy (mWh)

Month	2004	2005	2006	2007	2008
January	28,374	29,906	34,181	34,660	34,754
February	27,096	27,061	31,123	31,305	32,835
March	30,002	30,481	34,188	34,732	34,826
April	29,280	29,484	32,965	33,594	33,737
May	30,991	31,759	35,470	35,429	36,137
June	30,975	31,874	35,825	35,221	36,539
July	32,920	35,825	38,254	37,516	38,266
August	33,326	35,862	35,886	37,326	38,072
September	31,659	33,967	34,441	35,325	37,438
October	30,919	35,806	34,478	35,760	38,222
November	28,880	33,415	33,077	34,303	33,738
December	29,601	33,969	34,038	34,442	34,718
Total	364,022	389,408	413,925	419,612	429,284

Demand (kW)					
Month	2004	2005	2006	2007	2008
January	43,704	46,296	50,364	51,372	51,048
February	45,576	45,504	52,344	52,056	51,948
March	51,552	49,788	52,056	56,628	52,344
April	54,360	48,780	55,800	55,332	53,892
May	54,792	55,944	59,544	58,680	60,832
June	60,912	58,356	62,100	62,424	65,213
July	56,160	60,264	65,304	61,632	66,073
August	56,952	59,256	59,796	63,864	64,776
September	57,384	60,480	60,588	60,804	64,192
October	53,280	58,572	60,588	56,772	64,218
November	46,008	54,432	56,376	54,720	59,739
December	45,864	51,696	51,696	51,696	55,692
Total	626,544	649,368	686,556	685,980	709,966
Maximum	60,912	60,480	65,304	63,864	66,073

Table 4-3

**U. S. Department of Energy
Northern California Consortium
Lawrence Livermore National Laboratory
Energy and Demand Projections
2009 - 2013**

Energy (mWh)

Month	2009	2010	2011	2012	2013
January	35,706	36,064	36,064	36,064	36,064
February	34,788	35,136	35,136	35,136	35,136
March	35,781	36,138	36,138	36,138	36,138
April	34,609	34,955	34,955	34,955	34,955
May	36,499	36,864	36,864	36,864	36,864
June	36,905	37,274	37,274	37,274	37,274
July	38,649	39,035	39,035	39,035	39,035
August	38,453	38,838	38,838	38,838	38,838
September	37,812	38,190	38,190	38,190	38,190
October	39,587	40,951	40,951	40,951	40,951
November	35,856	37,512	37,512	37,512	37,512
December	35,266	36,556	36,556	36,556	36,556
Total	439,909	447,512	447,512	447,512	447,512

Demand (kW)

Month	2009	2010	2011	2012	2013
January	54,609	56,487	56,487	56,487	56,487
February	56,071	58,108	58,108	58,108	58,108
March	59,196	61,188	61,188	61,188	61,188
April	58,914	60,588	60,588	60,588	60,588
May	62,241	63,649	63,649	63,649	63,649
June	67,086	68,960	68,960	68,960	68,960
July	68,072	70,071	70,071	70,071	70,071
August	66,737	68,699	68,699	68,699	68,699
September	65,981	67,770	67,770	67,770	67,770
October	66,510	68,802	68,802	68,802	68,802
November	62,249	64,759	64,759	64,759	64,759
December	57,806	59,919	59,919	59,919	59,919
Total	745,471	769,000	769,000	769,000	769,000
Maximum	68,072	70,071	70,071	70,071	70,071

3. Current DSM Projects

For the past several years, LLNL has implemented numerous demand-side programs. The results in Table 4-4 show that programs implemented from FY 1997 through FY 2005 have produced annual energy savings of 17,900 mWh, reducing LLNL's power costs by \$1.4 million. The energy savings identified in Table 4-3 continue to be realized by the laboratory.

Table 4-4 Lawrence Livermore National Laboratory FY 1997 through 2005 Actual Project Summary Data Updates from 2004 IRP				
<u>Project</u>	<u>Date of Completion</u>	<u>Cost (\$, 000)</u>	<u>Annual Savings²</u>	
			<u>mWh</u>	<u>(\$, 000)</u>
Occupancy Sensors - Phase 2	Dec-1996	\$116.0	620	\$31.9
High Efficiency Lighting - Phase 5	Jan-1997	\$1,129.0	3,820	\$196.8
High Efficiency Lighting - Phase 6	May-1997	\$822.0	2,697	\$138.9
Total FY 1997		\$2,067.0	7,137	\$367.6
High Efficiency Lighting - Phase 5A	Jun-1998	\$361.0	361	\$18.6
Off Hours Direct Digital Control	Sep-1998	\$307.0	307	\$15.8
Total FY 1998		\$668.0	668	\$34.4
Install HVAC Energy Management System – B381 ¹	Sep-1999	\$240.9	1,776	\$273.8
HVAC Modifications (Various Buildings) ¹	Sep-1999	\$48.9	701	\$72.1
Total FY 1999		\$289.8	2,477	\$346.0
Chiller Condenser Water Temperature Reset	Oct-1999	\$73.1	1,056	\$54.4
B543 Restore Solar Domestic Hot Water System	Oct-1999	\$10.9	12.5	\$0.6
Compressed Air Distribution System Leak Repairs	Oct-1999	\$21.1	887	\$45.7
Upgrade HVAC Energy Management System - B131 ¹	Feb-2000	\$170.5	775	\$76.3
EXPAT Demo: Use P&T effluent in bldg heat pumps	Jun-2000	\$33.8	72	\$5.3
Central Plant Retrofits: Float condensate traps and LCW flow controls	Jul-2000	\$45.0	469	\$24.2
Compressed Air System Process Improvement	Sep-2000	\$52.8	1,153	\$59.4
Total FY 2000		\$407.1	4,424	\$265.8

Table 4-4 (Cont'd)

<u>Project</u>	<u>Date of Completion</u>	<u>Cost (\$, 000)</u>	<u>Annual Savings²</u>	
			<u>mWh</u>	<u>(\$,000)</u>
High Efficiency Motors 325PLCW – 1 & 12	Oct-2000	\$14.1	31	\$1.6
High Efficiency Motor for LCW Circulation Pump (350 HP)	Nov-2000	\$12.8	60	\$3.1
B482W & Part B482S Lighting Retrofit - T-8 Lamps and Delamping ¹	May-2000	\$59.4	341	\$20.4
Water and Energy Savings Automatic Urinal Flush Valves ¹	Sep-2001	\$63.5	23	\$22.8
Water and Energy Savings Ultra-Low Flow Toilets ¹	Sep-2001	\$52.7	15	\$15.1
B482N Lighting Retrofit: New Indirect Fluorescent Fixtures ¹	Sep-2001	\$89.3	265	\$17.2
Total FY 2001		\$291.7	735	\$80.2
B241 HVAC DDC Control Retrofit ¹	Sep-02	\$221.1	1,077	\$137.2
B291 Compressed Air High Pressure Alarm	Aug-02	\$10.3	114	(\$0.1)
VendingMizer Installations 85-devices installed in 47 buildings	May-02	\$21.5	110	\$5.7
WattStopper Isol� Plug Strips� 2,000 Plug-Load controllers	Jan-02	\$100.0	1,049	\$54.0
CA System Leak Survey & Repair UTel/MUD find and repair leaks	Jan-02	\$5.5	8.729	\$0.4
Drain-Down Recovery System (2002 Federal Energy Management Award)	May-02	\$14.9	0.266	\$61.8
Total FY 2002		\$373.4	2,360	\$259.1
Discovery (Visitors') Center Photovoltaic Demonstration	Apr-03	\$97.5	39	\$2.0
T1888/1889 PV Parking Lot & Walkway Lighting ²	Sep-03	\$133.7	15.42	\$0.4
Smart Motor Heater Retrofit at Central Plant U291	Sep-03	\$4.7	30.24	\$1.6
Total FY 2003		\$236.0	86	\$5.9
Waterless Urinal Pilot Program	Dec-04	\$17.2	2.63	\$3.9
Total FY 2005		\$17.2	2.63	\$3.9
Grand Total		\$4,350.1	17,889	\$1,360.9
^{1.} Dollar savings for these projects include electrical and natural gas savings calculated based on present Western electric power rates (August 2006) and trailing year average natural gas rates (August 2005 through July 2006).				
^{2.} 2002 EPA Region – 9 Green Government Award and 2003 DOE Departmental Energy Management Achievement Award				

LLNL has completed installation of its new TeraScale Computational Facility (TSF), and achieved significant reductions in load. Computations Directorate personnel took steps to reduce energy use by computer systems from original estimates by 50 percent, cutting electrical energy demand by 7.0 MW. This load reduction is equivalent to 11 percent of the laboratory's peak electrical demand. In these efforts, LLNL worked closely with IBM to encourage a more energy efficient design. Additionally, the facility cooling system, designed to industry norms was expected to use energy equivalent to 70 percent of the computer load. Records show that energy conserving practices like raising the temperature on the computer floors at TSF have resulted in the system using only 30 percent to 40 percent of the computer load without any adverse effects on the system.

4. Livermore Energy Savings Goals

LLNL has achieved the FY2005 goal and is on track to meet the 2010 goal. The laboratory's FY 2006 Performance towards EPA-2005 energy use reduction goals is as follows. During FY2006, LLNL took action to achieve an energy use reduction of 2.0 percent based on consumption during FY 2003, reaching a savings of 1.83 percent, almost meeting this new goal. Baseline and FY 2006 energy use and goal-oriented performance are summarized in Table 4-5 below.

Table 4-5

**LLNL FY 2006 Energy Use and Performance to
EPA-2005 Energy Use Reduction Goals**

<u>Description</u>	<u>FY 2003</u>	<u>FY 2006</u>	<u>Savings</u>
Electric Power (mWh)	321,919	307,772	4.39%
Green Credits (mWh)	0	13,220	-
Fuel Oil (K Gal)	12.41	0	100.00%
Natural Gas (MCF)	446,637	460,636	(3.13%)
LPG/Propane (K Gal)	0	5.11	-
Equivalent Energy (MBTU)	1560.6	1525.5	2.25%
Facilities Floor Area (K SF)	7,024.0	6,994.4	(0.42%)
Energy (BTU) / (K SF)	276.7	218.05	1.83%

Measures undertaken to reduce goal-oriented energy use included voluntary employee actions promoted in response to the President's Hurricane Relief Directive and by excluding the extraordinarily high electric power use of the new Terascale Computational Facility, the world's fastest computer system.

Renewable Energy. LLNL has purchased renewable energy credits (RECs) since FY 2005 and has limited self electric power generation capability via a grid-connected photovoltaic exhibit.

1. Self-Generated Renewable Energy.

Only a couple small scale self-generating renewable energy projects have been implemented at LLNL.

2. The LLNL Discovery [Visitor's] Center Photovoltaic (PV) Exhibit and installation of PV Parking Lot and Walkway Lighting at T1888/T1889 demonstrate and promote application of renewable power generation.

The small, demonstration scale, grid-connected, installation at the Discovery Center, has a maximum capacity of 10-kW, but has presently been built out only to 3.5-kW. The PV Exhibit has not been found to be life-cycle cost-effective. It was installed via DOE – Environmental Management funding for the purpose of promoting application of PV technology in the local community. During FY 2006, instrumentation indicates 3,855 kWh of power was generated. Based on the average cost of power at the Discovery Center, a direct PG&E account, cost savings totaled about \$540.

3. The LLNL Environmental Remediation Department has deployed a number of Solar Treatment Units (STU's) throughout the main site and Site-300. The STU's are photovoltaic-powered, portable, groundwater contamination treatment units.

Widespread application of PV power at LLNL's main site and Site 300 is not presently cost effective due to the relatively high cost of PV power compared with the cost of wholesale power purchases.

LLNL has several smaller power supply contracts with PG&E, including the Visitor's Center and the MOCHO Pump Station. The Visitor's Center PV Exhibit described above has been installed on one of these accounts. The application of PV power at the remote MOCHO Pump Station and at the main site has been evaluated twice via Super – Energy Savings Performance Contract (ESPC) project Initial Proposals submitted to LLNL during FY 2005 and FY 2007. Analyses indicate installation of PV at LLNL is not life-cycle cost-effective.

5. New Projects

LLNL is planning to implement two ESPC measures, HVAC Controls & Electric Metering. Other energy savings action items have been identified and are in the process of implementation. Projects that have been selected for implementation include:

- Turn off CPUs when not needed. Change Laboratory-wide CPU backups and updates to accommodate sleep/hibernate modes.
- Virtual Computer Servers: fast-track conversion of Laboratory-wide computer servers to virtual servers.
- Chiller CHW water supply temperatures Lab-wide. Set building HVAC controls for unoccupied period temperature set-back / set-up.
- Set building HVAC controls for unoccupied period temperature set-back / set-up.
- Secure boilers during non-heating season.
- Assure lighting is turned off during unoccupied periods.
- Move Out of Office Trailers: move to permanent facilities; secure energy supplies to trailers.
- B132 N & S Lighting Retrofit: In-House Implementation.

We have been able to quantify the impact of the B132N Retrofit project and the HVAC controls project. Over the next few years, these projects would save 9,500 mWh annually. The results are summarized in Table 4-6.

TABLE 4-6

**Lawrence Livermore National Laboratory
New Projects**

<u>Project</u>	<u>Completion Date</u>	<u>Total Project Cost (\$, 000)</u>	<u>Annual Saving</u>	
			<u>(mWh)</u>	<u>(\$, 000)</u>
B132N Re-Lamp Project	Sept. 2008	50	56.7	\$3.9
Super-ESPC Project: HVAC Controls & Electric Metering	2011	13,400	9,445	1,042
Total		13,450	9,501.7	\$1,045.9

6. Impact of Conservation and Other Demand-Side Programs

Tables 4-7 and 4-8 show the impact of demand-side programs upon LLNL's demand and energy projections.

Table 4-7 Lawrence Livermore National Laboratory Demand Projections (kW)			
<u>Fiscal Year</u>	<u>Base Case Projected Demand</u>	<u>Cumulative Estimated Savings</u>	<u>Net Demand Requirements</u>
2008	70,518	4,445	66,073
2009	72,517	4,445	68,072
2010	74,516	4,445	70,071
2011	74,516	4,445	70,071
2012	74,516	4,445	70,071
2013	74,516	4,445	70,071
2014	74,516	4,445	70,071

Table 4-8 Lawrence Livermore National Laboratory Energy Projections (mWh)			
<u>Fiscal Year</u>	<u>Base Case Energy Projections</u>	<u>Cumulative Estimated Savings</u>	<u>Net Energy Requirements</u>
2008	444,997	17,888	427,109
2009	453,768	17,888	435,880
2010	461,089	17,888	443,201
2011	465,189	17,888	447,301
2012	465,189	17,888	447,301
2013	465,189	17,888	447,301
2014	465,189	17,888	447,301
2015	465,189	17,888	447,301

SECTION 5
SITE 300

1. Introduction

Site 300 is part of the National Nuclear Security Agency's (NNSA) complex at Livermore, California. Site 300 is located 15 miles southeast of the LLNL main site. The site is not connected electrically to the main LLNL facility. Western supplies electricity to Site 300 using the transmission grid controlled by the ISO. Site 300 shares in the Consortium's CVP entitlement and third party contracts purchased on DOE's behalf by Western.

Table 5-1 shows Site 300's actual demand and energy usage during the FY 2005 – FY 2007 period. Table 5-1 also shows Site 300's expenditures on electric energy during that time.

Table 5-1			
U. S. Department of Energy Northern California Consortium			
SITE 300			
<u>Data Summary</u>	<u>FY 2005</u>	<u>FY 2006</u>	<u>FY 2007</u>
Total Energy (mWh) *	16,065	14,904	14,715
Peak Demand (kW)	3,060	2,928	2,598
Electricity Expenditures	\$766,075	\$708,508	\$771,144
* Total Energy (mWh) data is limited to electric power provided by Western for the federal fiscal years, commencing in October, each year.			

2. Actual and Forecast Demands and Energy

Table 5-2 shows Site 300's actual demand and energy during the period 2004 – April 2008. (Table 5-2 shows estimated demand and energy data for the May – December 2008 period.) Table 5-3 shows Site 300's projected demand and energy during the 2009 – 2013 period.

Table-5-2

**U. S. Department of Energy
Northern California Consortium**

**SITE 300
Energy and Demand
Actual 2004 - 2008
Energy (mWh)**

Month	2004	2005	2006	2007	2008
January	1,559	1,732	1,477	1,471	1,515
February	1,449	1,290	1,285	1,331	1,234
March	1,357	1,356	1,510	1,224	1,152
April	1,231	1,323	1,239	1,147	1,037
May	1,278	1,284	1,172	1,148	1,171
June	1,166	1,189	1,126	1,149	1,172
July	1,246	1,290	1,228	1,154	1,177
August	1,193	1,186	1,113	1,198	1,222
September	1,185	1,100	1,113	1,149	1,208
October	1,271	1,122	1,127	1,174	1,149
November	1,438	1,185	1,225	1,183	1,249
December	1,606	1,334	1,379	1,472	1,407
Total	15,981	15,390	14,994	14,801	14,695

Demand (kW)

Month	2004	2005	2006	2007	2008
January	2,844	2,928	2,760	3,078	2,730
February	2,928	2,616	2,928	2,766	2,622
March	2,652	2,550	2,880	2,784	2,286
April	2,736	2,544	2,586	2,598	2,112
May	2,568	2,364	2,232	2,052	2,365
June	2,232	2,364	2,406	2,712	2,607
July	2,364	2,448	2,376	2,544	2,468
August	2,640	2,460	2,220	2,622	2,535
September	2,472	2,280	2,136	2,154	2,278
October	2,448	2,220	1,992	2,124	2,646
November	3,060	2,238	2,538	2,322	2,731
December	2,904	2,904	2,820	2,820	2,914
Total	31,848	29,916	29,874	30,576	30,295
Maximum	3,060	2,928	2,928	3,078	2,914

Table 5-3

**U. S. Department of Energy
Northern California Consortium**

**SITE 300
Energy and Demand Projections
2009 - 2013
Energy (mWh)**

Month	2009	2010	2011	2012	2013
January	1,516	1,531	1,531	1,531	1,531
February	1,371	1,385	1,385	1,385	1,385
March	1,261	1,273	1,273	1,273	1,273
April	1,182	1,194	1,194	1,194	1,194
May	1,183	1,195	1,195	1,195	1,195
June	1,184	1,196	1,196	1,196	1,196
July	1,189	1,201	1,201	1,201	1,201
August	1,234	1,247	1,247	1,247	1,247
September	1,220	1,232	1,232	1,232	1,232
October	1,161	1,172	1,172	1,172	1,172
November	1,262	1,274	1,274	1,274	1,274
December	1,421	1,435	1,435	1,435	1,435
Total	15,183	15,335	15,335	15,335	15,335

Demand (kW)

Month	2009	2010	2011	2012	2013
January	2,954	2,966	2,966	2,966	2,966
February	2,953	2,979	2,979	2,979	2,979
March	2,833	2,850	2,850	2,850	2,850
April	2,790	2,826	2,826	2,826	2,826
May	2,368	2,372	2,372	2,372	2,372
June	2,632	2,656	2,656	2,656	2,656
July	2,464	2,459	2,459	2,459	2,459
August	2,531	2,526	2,526	2,526	2,526
September	2,277	2,277	2,277	2,277	2,277
October	2,684	2,722	2,722	2,722	2,722
November	2,775	2,819	2,819	2,819	2,819
December	2,933	2,953	2,953	2,953	2,953
Total	32,192	32,404	32,404	32,404	32,404
Maximum	2,954	2,979	2,979	2,979	2,979

3. Current DSM Projects

Table 5-4 shows the DSM projects currently in place at Site 300. A heating, ventilation and air conditioning (HVAC), direct digital controls (DDC) retrofit was completed at Site 300 during FY 2005, the first new energy efficiency/demand-side management project implemented since the FY 1999 IRP for Site 300.

TABLE 5-4

**U. S. Department of Energy
Northern California Consortium**

**SITE 300
FY 1998 Actual Project Summary Data**

<u>Project</u>	<u>Completion Date</u>	<u>Cost (\$, 000)</u>	<u>Annual Savings</u>	
			<u>(mWh)</u>	<u>(\$, 000)</u>
High Efficiency Lighting - Phase 5A	June 1998	186	1,299	69.9
HVAC – DDC Controls Retrofit – Various Buildings	Sept. 2005	275	1,570	80.9
Total by end of FY 2005		\$461	2,869	\$150.8

Note: Dollar savings for these projects include electrical savings. Energy cost savings are updated with WAPA's electric power rates as of August 2006.

Renewable Energy Credits. Site 300 has also taken administrative actions to achieve energy reduction goals that include the purchase of renewable energy credits (RECs). LLNL commenced the purchase of RECs from Western with 576.7-mWh per year for five-years, starting in FY 2005. The purchase of RECs helps the laboratory achieve EO 13123 / DOE O 430.2A energy use reduction goals as a credit is allowed in reporting electric power use equal to that purchased as RECs. This REC credit is not available to help in achieving EPA-2005 energy use reduction goals; rather, EPA-2005 separately requires federal facilities to purchase renewable energy.

4. New Projects

Site 300 does not plan to implement any new demand-side programs over the next several years. Current programs bring Site 300's energy conservation efforts into compliance with EO 12423.

5. Impact of Demand-Side Program

The forecast of Site 300's future electric power requirements included in the 2004 IRP has been updated based on the most recent data available. Table 5-6 shows projections of the laboratory's demand requirements without the High Efficiency Lighting project and the reductions in demand requirements due to the implementation of the project, and actual and projected demand requirements net of these measures. Table 5-7 shows projections of the Laboratory's energy requirements without the High Efficiency Lighting project and the reductions in energy requirements due to the implementation of the project, and actual and projected energy need net of these measures.

TABLE 5-5

**U. S. Department of Energy
Northern California Consortium**

**SITE 300
DEMAND PROJECTIONS
(kW)**

<u>Fiscal Year</u>	<u>Base Case Projected Demand</u>	<u>Cumulative Estimated Savings</u>	<u>Net Demand Requirements</u>
2006	3,661	423	3,238
2007	3,757	423	3,334
2008	3,853	423	3,430
2009	3,949	423	3,526
2010	3,949	423	3,526
2011	3,949	423	3,526
2012	3,949	423	3,526
2013	3,949	423	3,526
2014	3,949	423	3,526
2015	3,949	423	3,526

TABLE 5-6**U. S. Department of Energy
Northern California Consortium****SITE 300
ENERGY PROJECTIONS
(mWh)**

<u>Fiscal Year</u>	<u>Base Case Energy Projections</u>	<u>Cumulative Estimated Savings</u>	<u>Net Energy Requirements</u>
2006	21,459	3,734	17,725
2007	22,249	3,734	18,515
2008	23,333	3,734	19,599
2009	23,424	3,734	19,690
2010	23,424	3,734	19,690
2011	23,424	3,734	19,690
2012	23,424	3,734	19,690
2013	23,424	3,734	19,690
2014	23,424	3,734	19,690
2015	23,424	3,734	19,690

SECTION 6

STANFORD LINEAR ACCELERATOR CENTER

1. Introduction

The Stanford Linear Accelerator Center (SLAC) is a federally funded scientific research facility with major programs in photon science, high energy particle physics, and astrophysics. Located at Stanford University in Menlo Park, California, SLAC operates state of the art particle beam accelerators and related facilities for use in high-energy physics and synchrotron radiation research. The Linear Coherent Light Source (LCLS), which builds on the 2-mile linear accelerator, is currently under construction and will be the primary SLAC research facility in the coming decade.

SLAC receives all of its electricity under arrangements between DOE's Berkeley Site Office and Western. A portion of this power is from the Consortium's entitlement to CVP power marketed by Western. The balance of SLAC's resources is from a share of third party contracts Western secured acting as an agent for the Consortium. Power is delivered to SLAC over the transmission grid controlled by the California Independent System Operator (ISO). This section of the report focuses on SLAC's demand-side activities, since supply-side resources are secured under the auspices of the Berkeley Site Office acting on behalf of all of DOE's Northern California Laboratories.

The remainder of this section is organized as follows: Section 2 presents actual and forecasted demand and energy data. Section 3 reports the results of current demand-side conservation and energy efficiency measures in place at SLAC and their effect upon energy savings. Section 4 identifies demand-side measures to be considered to comply with DOE's requirements for reductions in energy usage in the future. The report also includes as an attachment a preliminary screening study undertaken on behalf of SLAC to identify the economic viability of various renewable energy alternatives.

2. Actual and Forecast Demands and Energy

SLAC's actual projected load data are in Tables 6-1 and 6-2 below. These projections are based on an anticipated scientific research program that is subject to change, depending on future funding levels.

Table 6-1

**U. S. Department of Energy
Northern California Consortium
Stanford Linear Accelerator Center
Actual Energy and Demand
2004 - 2008**

Month	Energy (mWh)				
	2004	2005	2006	2007	2008
January	32,578	11,234	32,466	25,661	39,267
February	33,595	11,170	30,716	32,466	38,780
March	36,547	16,536	33,879	37,268	40,317
April	35,756	31,525	36,781	34,481	19,900
May	37,587	30,936	34,433	29,945	17,700
June	35,846	35,078	37,015	38,948	17,200
July	38,474	37,148	38,744	42,352	17,700
August	6,354	35,593	24,511	40,582	16,200
September	10,010	36,220	5,310	9,271	12,400
October	14,323	18,651	7,828	9,013	12,400
November	10,344	25,537	10,329	11,622	16,400
December	10,739	37,198	11,755	30,610	17,000
Total	302,152	326,826	303,766	342,219	265,263

Month	Demand (kW)				
	2004	2005	2006	2007	2008
January	43,704	18,267	53,499	49,707	59,748
February	45,576	18,336	54,660	59,499	60,612
March	51,552	38,400	55,524	59,451	62,436
April	54,360	52,512	59,067	59,586	64,500
May	54,792	53,568	59,355	58,011	24,900
June	60,912	57,252	59,355	62,322	24,900
July	56,160	56,523	59,499	63,618	24,900
August	56,952	57,291	58,260	63,243	24,900
September	57,384	57,723	9,621	54,315	17,900
October	53,280	55,803	15,531	30,981	19,100
November	46,008	53,979	17,883	25,458	24,800
December	45,864	56,235	18,834	54,084	24,800
Total	626,544	575,889	521,088	640,275	433,496
Maximum	60,912	57,723	59,499	63,618	64,500

Table 6-2

**U. S. Department of Energy
Northern California Consortium
SLAC
Energy and Demand Projections
2009 - 2013**

Energy (mWh)					
Month	2009	2010	2011	2012	2013
January	17,000	20,000	24,000	24,000	24,000
February	15,500	18,700	23,200	23,200	23,200
March	17,100	20,600	25,700	25,700	25,700
April	19,500	24,900	24,900	24,900	24,900
May	20,100	25,700	20,600	20,600	20,600
June	19,500	20,000	20,000	20,000	20,000
July	20,100	20,600	20,600	20,600	20,600
August	11,200	11,600	11,600	11,600	11,600
September	10,900	11,200	11,200	11,200	11,200
October	19,000	19,000	19,000	19,000	19,000
November	19,400	19,400	19,400	19,400	19,400
December	19,000	19,000	19,000	19,000	19,000
Total	208,300	230,700	239,200	239,200	239,200
Demand (kW)					
Month	2009	2010	2011	2012	2013
January	24,800	29,900	38,500	38,500	38,500
February	24,900	29,900	38,500	38,500	38,500
March	24,800	29,900	38,500	38,500	38,500
April	29,900	38,500	38,500	38,500	38,500
May	29,800	38,500	29,900	29,900	29,900
June	29,900	29,900	29,900	29,900	29,900
July	29,800	29,900	29,900	29,900	29,900
August	15,600	16,200	16,200	16,200	16,200
September	15,700	16,200	16,200	16,200	16,200
October	29,700	29,700	29,700	29,700	29,700
November	29,900	29,900	29,900	29,900	29,900
December	29,900	29,900	29,900	29,900	29,900
Total	314,700	348,400	365,600	365,600	365,600
Maximum	29,900	38,500	38,500	38,500	38,500

3. Current DSM Energy Efficiency and Renewable Resource Projects.

Over the past several years, SLAC has undertaken numerous demand-side efficiency projects. Table 6-3 shows projects completed and in place through FY 2004. These projects provide 20,400 mWh of annual energy savings, with annual dollar savings amounting to \$1.2 million. The cost of these projects was \$6.0 million.

Table 6-3
Actual Data for Projects Completed Prior to 2004

Project	Completion Date	Total Project Cost (\$ 000)	Annual Savings	
			mWh	(\$ 000)
Remote Monitoring & Control of Utility Systems for Linac	September 1998	\$2,140	8,475	\$428
HV AC Direct Digital Control System – Phase 2	May 1999	\$1,207	3,920	\$198
Installation of programmable thermostats at packaged HVAC units	September 1999	\$23	63	\$3.2
HV AC Direct Digital Control System – Phase 3	September 2000	\$162.0	296	\$14.9
Replacement of one Multi-Zone Air Handling unit (MZ-621) at Building 025	October 2000	\$160	554	\$28
Lighting Control with DDC EMS – Building 041, 1 st Floor	June 2001	\$16.0	102	\$5.2
Replacement of High-Bay Lighting at Building 026	August 2001	\$29	141	\$7.1
Lighting Control with DDC EMS – Building 041, 2 nd Floor	May 2002	\$23	89	\$4.5
Central Chilled Water Plant Upgrade	May 2002	\$1,390	2,316	\$117
Klystron Gallery Lighting Upgrade - Phase 1	September 2002	\$430.5	3,611	\$182.4
Klystron Gallery Lighting Upgrade – Phase 2	May 2003	\$125	845	\$42.7
Computer Center DDC Energy Management System Upgrade	August 2003	\$69	250	\$12.6
Accelerator Housing Lighting Control Modifications	May 2004	\$77.3	355	\$17.9
Test Lab High-Bay Lighting Replacement	September 2004	\$35.6	155	\$7.6
Low Conductivity Water systems decommissioning – North and South Focusing Magnets of SLAC Linear Collider (SLC)	June 2004	\$11.5	1,748	\$88.3
Replacement of obsolete Variable Frequency Drives at 10 fan motors of SLAC Computer Center	July 2004	\$50.5	277	\$14.0
Installation of Variable Frequency Drive at 125 HP fan motor of CT 1701	August 2004	\$26.3	245	\$12.4
Totals		\$5,976	20,442	\$1,184

More recently, over the past two fiscal years, SLAC has implemented additional energy-efficiency projects and is currently investigating ESPC third party financing for other energy conservation measures. Table 6-4 illustrates the projects SLAC completed during the period between FY 2006 and FY 2007². The projects completed during this time cost \$802,000 and reduced SLAC's usage by collectively contribute 1,252 mWh while saving.

Noteworthy energy conservation projects completed in FY06-07 include: (1) lighting efficiency upgrade projects for Building 084, Building 081, and Building 040 Central Lab, (2) HVAC upgrades to Building 025, (3) DDC Environmental Controls at B040 and B041, and (4) high efficiency pump motors at the B005 Cooling Tower. HVAC and lighting upgrades in the Main Control Center (Building 005) were completed in FY 2008.


<p align="center">Table 6-4</p> <p align="center">Stanford Linear Accelerator Center</p> <p align="center">2006 and 2007 Energy Savings Projects</p>				
<u>Project</u>	<u>Completion Date</u>	<u>Cost (\$000)</u>	<u>Annual Saving (mWh)</u>	<u>(\$000)</u>
Site Interior Lighting Upgrade – Phase 1	Aug. 2006	260	276	14.9
DDC EMS Upgrade	July 2006	86	200	10.8
Replacement of Central Fans and Cooling Coils - Computer Center, B050	July 2006	270	321	17.4
Total		802	1,252	67.7

² No DSM projects were undertaken during FY 2005, because of an overall review of electric operation and maintenance practices.

4. Current Laboratory Goals and EO 13123 Impacts

SLAC has entered a period of transition, supporting both High-Energy Physics (HEP) and Basic Energy Sciences (BES) programs within the DOE's Office of Science. The PEP-II accelerator program ended in FY2008, resulting in a significant reduction in SLAC's total electrical load. The new Linear Coherent Light Source (LCLS) project is under construction and will lead to small gradual increases in electrical loads in the next few years, but not to the levels seen during the PEP-II era. Figure 6-4 illustrates future energy estimates.

Figure 6-4



Executive Order 13423 - Strengthening Federal Environmental, Energy, and Transportation Management supersedes EO 13123 and provides an improved alternative for federal agencies to manage energy toward specific goals. DOE has responded to this Executive Order with the TEAM Initiative. In response to these requirements, SLAC will put into place an executable plan, as required by the initiative, to help achieve the following goals:

1. 30 percent non-programmatic energy reduction by 2015
2. Water reductions of 16 percent by 2015
3. Renewable energy consumption levels >7.5 percent

4. All new construction >\$5M will be LEED Gold Certified
5. 15 percent of facility building profile will be LEED Gold by 2015

These target goals, and others, will be contained within SLAC's executable plan. In addition to the executable plan, the current Performance Evaluation Measurement Plan (PEMP) contains goals linked to the TEAM Initiative and reflects the targets established by EO 13423.

In addition to the DOE compliance goals and objectives, SLAC is initiating an Infrastructure Modernization Proposal which will change the complexion of the facilities to more adequately support the culture and vision of the laboratory. The plan includes the addition of a new research building (56k square feet), modernization of three existing buildings (65k square feet), the demolition of substandard trailers (57k square feet) and the addition of a new computer center. These improvements will help SLAC gain efficiencies in energy management as the buildings will be LEED Certified and replace inefficient legacy systems.

5. Projected DSM / Energy Efficiency / Renewable Resource Projects

Several energy conservation measures (ECM) are currently being studied or are in various stages of implementation. Among these are:

- Improving process cooling water distribution system efficiencies
- Adding an advanced metering system that can be used for energy management
- Upgrading HVAC equipment and controls systems to improve efficiency
- Upgrading lighting systems to improve efficiency

Currently, SLAC is proceeding with the conceptual design and cost estimate of a new advanced power monitoring system in accordance with DOE O 430.2B. The plan was complete and submitted to the DOE in FY2007. When installed, this system will provide SLAC with data required to make informed decisions in energy management. The estimated savings resulting from the installation of advanced meters is between

2 and 3 percent. This is a number accepted by the DOE and is derived from the implied results of the Hawthorne Effect.

Additionally, SLAC began its evaluation of energy service companies (ESCOs) in 2007 in conformance with the DOE TEAM Initiatives and the DOE FEMP Super Energy Savings Performance Contracting process. A steering committee was formed to review the pre-approved ESCOs and a selection process was initiated. NORESKO, an energy services company with western regional headquarters in Irvine, CA, was given direction to develop an initial proposal which was presented to SLAC in February 2008. General site-wide energy surveys have been completed and an informal report of findings was produced with twelve proposed energy conservation measure projects. Each of the ECMs in this initial proposal is currently being reviewed for its potential benefits.

A comprehensive listing of the DSM conservation measures that were proposed and are under consideration are described below. SLAC is in the process of moving forward with a limited detailed energy survey intended to evaluate selected projects within the proposed ECM listing. The selected Super ESPC delivery order project design and construction activities are tentatively scheduled to commence in FY2009.

ECM 01 – Lighting Upgrade (\$2.37M): Replace existing fluorescent and HID fixtures with T-8 high efficiency lighting. This ECM will include 72 buildings and has an estimated annual savings return of 5.85 gWh - \$361,268.

ECM 02 – Water Conservation (\$322k): Replace existing water fixtures, site wide, with high efficiency ultra low flow devices. This ECM will save an estimated 3,595 kgal of water and 679 therms of natural gas annually. - \$27,510.

ECM 03 – Advanced Metering (\$828k): Metering of electricity, water and natural gas for non-process support buildings that fall within the metering guidelines published by FEMP (31 buildings total). A 2.5 percent reduction of service loads is estimated for each commodity - \$65,870.

ECM 04 – Boiler Combustion Controls and VFDs (\$287k): Replace obsolete linkage style controls with digital controls connected to automated logic control system for enhanced fuel flow, air flow, stack temp, and energy use. This ECM will reduce

electrical load by an estimated 207,935 kWh and natural gas load by 19,179 therms - \$28,691.

ECM 05 – Chilled Water Flow Control and Plant Modifications (\$498k): Replace existing chilled water control valves with flow limited two-way valves minimizing supply dilution and enhancing secondary loop efficiency. This ECM includes replacing an estimated 178 valves and has been estimated to save 507,437 kWh of electrical energy - \$30,905.

ECM 06 – Solar Photovoltaic System (cost unknown): Install a nominal 1MW solar array on the klystron gallery roof paid for through an energy services agreement. This system could help SLAC add approximately 1 percent to the on-site renewable energy requirements of the TEAM Initiative while saving an estimated annual 1.5 gWh.

ECM 07 – Variable Speed Cooling Tower Fans (\$475k): Replace existing constant speed and three speed fans in six major cooling towers with VFDs and VFD compatible motors. This ECM will save an estimated 1.04 GWh of electrical energy - \$63,292.

ECM 08 – Variable Speed Cooling Tower Pumps (\$2.5M): Add new VFDs and VFD compatible motors and control components to seven cooling tower water distribution systems. This ECM will save an estimated 5.18 GWh of electrical energy - \$315,300.

ECM 09 – Low Conductivity Water Pumping (\$1.3M): Install VFD's, VFD compatible motors, and system control features capable of limiting flow rates to required levels in areas where needed and reducing the flow rates in accelerator systems not currently in use. This ECM has an estimated savings of electrical power in the 5.85 gWh range - \$355,980.

ECM 10 – B118 Chiller Replacement (\$385k): Replace inefficient aged chiller and reconfigure the control systems to optimize load capacity. This ECM has an estimated potential savings of 153,898 kWh of electricity - \$9,372.

ECM 11 – Recommission HVAC Controls (\$3.6M): Review and readjust all digital control system algorithms, sensors, devices and repair or replace as necessary any broken or defective control components. Duct sealing will be evaluated for potential

savings during the detailed energy survey phase of this ECM. The total estimated energy savings includes 1.57 GWh of electricity and 16,781 therms excluding any duct sealing estimates which could increase the estimated 3.5 percent savings substantially reducing ROI term - \$109,847.

ECM 12 – Duct Sealing (Unknown): Duct sealing will be evaluated for implementation during the detailed energy survey consistent with those guidelines established at the Lawrence Berkeley National Lab. Initial studies at LBNL reveal a potential for 30 percent reduction in fan speed and 65 percent reduction in fan power requirements on buildings with > 10 percent duct leakage. Leakage evaluations are to be performed in the detailed energy survey.

These proposed ECMs above are summarized in Table 6-5.

Table 6-5
ESPC Project Initial Proposal ECM Listing

No.	Description	electrical energy kWh/yr	natural gas therms/yr	Water kgal/yr	Sewer kgal/yr	Maint Savings	Annual Savings
ECM 001	Lighting >	5,850,042				5,000 >	\$361,268
ECM 002	Water Conservation >		679	3,595	3,595	>	\$27,510
ECM 003	Advanced Metering >	943,821	9,589	113		>	\$65,870
ECM 004	Boiler Combustion Controls >	207,935	19,179			>	\$28,691
ECM 005	CHW Flow Control/Plant Mods >	507,473				>	\$30,905
ECM 006	Photovoltaic Power >	1,481,667				>	\$90,234
ECM 007	CT Fans >	1,039,275				>	\$63,292
ECM 008	CTW Pumping >	5,177,344				>	\$315,300
ECM 009	LCW Pumping >	5,845,315				>	\$355,980
ECM 010	B118 Chiller Replacement >	153,898				>	\$9,372
ECM 011	Controls Tune/HVAC mods >	1,573,457	16,781			>	\$109,847
ECM 012	Repair Leaking HWS piping >		14,940	1,062		>	\$15,682
<i>totals</i> >		21,298,560	46,229	3,708	3,595	5,000 >	\$1,368,035

Note: The annual cost savings are calculated based upon projections of electrical rates with estimated escalation factors.

Additional Studies, Reports, and Other Analyses. In response to the Department of Energy Order 430.2B, SLAC conducted its evaluation of third party financing alternatives for energy reduction projects and selected NORESO to submit an initial ESPC proposal. This proposal was initiated in late FY 2007 and received from

NORESCO in March of 2008. The initial proposal includes a high level site wide survey of the energy consuming systems, an analysis of these systems, and a list of proposed conservation measures and the estimated potential energy savings. Included in the initial submittal are twelve energy conservation measures for consideration and an analysis of SLAC's energy consumption on a programmatic versus non-programmatic basis. SLAC is currently reviewing the proposal and will move forward with those measures that are judged to be cost effective and compatible with other institutional plans and requirements.

Renewable Energy Evaluations. In addition to the Super ESPC initial proposal report, a detailed engineering evaluation by Antares Engineers and Economists released in May 2008 provides a renewable energy site assessment for SLAC. The executive summary of this report is attached.

In 2006 a lighting survey was conducted at SLAC for buildings 005, 026, 061, 062, 081, 120 and 131. The purpose of the audit was to gain information on the existing lighting systems, recommend new enhanced efficiency lighting system components, and then calculate estimated savings in light and thermal energy as a result of the proposed installation. This study and others were provided to NORESO and incorporated into the initial proposal activities and presentation package.


ATTACHMENT TO SECTION 6

**Stanford Linear Accelerator Center (SLAC)
Antares Renewable Energy Site Assessment
(May 2008)**



Stanford Linear Accelerator Center Renewable Energy Site Assessment Draft Report

Contract 20.007.01
Reference:
Prepared by: ANTARES Group Inc.
Prepared for: U.S. Department of Energy
Date: May 23, 2008



EXECUTIVE SUMMARY

As part of the Transformational Energy Action Management (TEAM) Initiative, DOE FEMP requested technical assistance to perform an assessment of on-site renewable energy opportunities at Stanford Linear Accelerator Center in Menlo Park, CA. This assessment includes an analysis of potential opportunities for several renewable energy technologies, including: solar photovoltaics, solar thermal, active daylighting, wind turbines, and biomass energy projects.

Antares staff performed a site visit on April 9, 2008. The primary purpose of the site visit was to gather the necessary data to perform economic and technical analyses for potential on-site renewable energy installations.

The report considers options for financing, potential project sizes, and various technologies to determine which cases, if any, will be economically justifiable over a 25 year period. Sensitivities to the availability of various incentives and RECs are also explored in this study. The result of the renewable energy analyses conducted for the site indicate the following:

- **SOLAR PV** - Several potential sites for PV development were identified. These sites included roof top and ground mounted locations. Solar PV lighting options are also discussed. The resulting economic analyses suggest that none of the projects reviewed would result in energy savings at the site on a life-cycle cost basis. However, a ground mounted Concentrating PV (CPV) project could have acceptable simple payback period (i.e. no discounting factor) under 25 years.
- **DAYLIGHTING** - An active solar daylighting installation was analyzed for the Klystron Gallery, as it is a large area with constant lighting loads. This analysis suggests that this application would have a long but potentially acceptable payback period.
- **SOLAR THERMAL** - The only solar thermal project that was investigated for SLAC was a solar hot water system at the cafeteria, as there are no other buildings with significant hot water loads and air-preheating technologies do not apply in this climate. This analysis suggests that solar hot water heating for the cafeteria building has a long, but potentially acceptable payback period.
- **WIND ENERGY PROJECTS** - There is little potential to develop a commercially significant or economically justifiable wind project at SLAC. Windspeed data available from the Stanford Wind Energy Project (SWEP) was used to estimate wind energy potentials. These data suggest that average wind velocities are far too low for a wind energy project to be feasible.
- **BIOMASS ENERGY** - There does not seem to be much potential to develop a biomass energy facility on site. SLAC is located in a non-attainment area, which would be a very large barrier for permitting. Additionally, there is not enough available area near the central boiler facility to support the storage and handling of biomass that would be required for a biomass energy project.

A summary of the life cycle cost analysis for considered PV technologies based on an ESPC or PPA agreement with a 25 year term is shown in Exhibit 1 below. Analysis results for the active daylighting system and cafeteria solar hot water system are given in Exhibit 2 and Exhibit 3, respectively.

Project lifetime, PPA contract lifetime (through WAPA), and ESPC contract lifetimes in these analyses are all assumed to be 25 years. The lifecycle costs for the renewable energy systems are compared with the cost of purchasing energy for 25 years (status quo) in the tables. The analysis results for PV systems depend on selling / swapping solar RECs, for a value of \$0.06/kWh. It is also assumed that the site will receive the double bonus for renewable energy production on-site, as described in the FEMP Guidance document (US Department of Energy FEMP 2007).

Estimated electricity production and current and constant levelized costs of electricity (LCOE) for the PV systems are shown in Exhibit 1. For comparison, SLAC's FY 2008 annual electricity consumption was 247.9 GWh. The on-site electricity is provided by WAPA, and currently costs \$0.059/kWh but is projected to cost \$0.079 in 2009.³

Based on this analysis, there is potential for installing new renewable energy generation via photovoltaic, active daylighting, solar thermal systems at SLAC. A 25 year PPA agreement has the best results for all cases. However, if the ESCo bundled smaller renewable energy project with other energy conservation measures (ECMs), it may improve overall economic viability.

The systems with the lowest payback periods are the ground-mount Concentrating PV system south of the Klystron Gallery ("the Gallery"), active daylighting installation at the Gallery, and a Solar Hot Water system at the Cafeteria.

The 1 MW CPV system in the open area south of the Klystron Gallery would generate about 1.5 GWh of electricity annually, for a constant levelized cost of \$0.11/kWh (for PPA financing with incentives and RECs). Although generating PV power at such rates is very reasonable, the low cost of WAPA power does present a challenge. At the production cost level, the PV array would generate electricity at \$0.05/kWh more than the current price for WAPA electricity, or \$0.03/kWh more than the projected 2009 electricity cost. Although this disparity is projected to be erased in out years, the parity comes too late to rescue the LCC economics. Over the 25-year lifetime, the CPV system would cost \$1.3 million dollars more than status quo.

That said, the reviewed project is relatively large and the resulting economics could be attractive if different contract or market mechanisms could be identified that further enhance the results. This may include reviewing alternate project structures and different approaches to value the RECs. The project could also be scaled up to offset more of the grid-tied energy consumption on-site.

It is important to note that the PV economic results are based on installed cost estimates from Antares in-house resources and recent vendor quotes, and are somewhat higher than the installed costs used by NREL in DOE site assessments. For comparative purposes, an alternate economic analysis for these PV systems has been performed using installed costs based the NREL values. These results are given in Appendix A.

³ Projected cost is weighted for peak and off-peak electricity costs from Exeter analysis, as appropriate for solar projects that operate during daylight hours.

Exhibit 1 Life Cycle Cost Analysis Results - PV Systems

		Roof Mounted PV	Klystron Gallery (thin film)	Ground Mount PV	Ground Mount CPV
	Electricity Production (MWh/yr)	368.1	989.1	1,890	1,506
	Installed Capital Cost (\$000) (1)	\$2,354	\$5,940	\$11,500	\$5,500
	2009 Electricity Cost (\$/kWh)	\$0.079	\$0.079	\$0.079	\$0.079
	Year 1 Energy Savings (\$000)	\$29.16	\$78.36	\$149.7	\$119.3
	25 Year Status Quo LCC (\$000) (2)	\$523.4	\$1,406	\$2,688	\$2,141
All Incentives and RECs					
ESPC (25 years)	1st Yr Undiscounted Savings (\$000) (3)	\$69.33	\$186.95	\$336.30	\$261.45
	System LCC (\$000)	\$1,650	\$3,850	\$7,637	\$3,439
	Current \$ LCOE	\$0.35	\$0.31	\$0.32	\$0.19
	Constant \$ LCOE	\$0.29	\$0.25	\$0.26	\$0.16
	Simple Payback	43 years	37 years	39 years	24 years
PPA (25 years)	System LCC(\$000)	\$1,683	\$3,943	\$7,859	\$3,487
	Current \$ LCOE	\$0.26	\$0.23	\$0.24	\$0.13
	Constant \$ LCOE	\$0.22	\$0.19	\$0.20	\$0.11
	Simple Payback	37 years	27 years	28 years	19 years

(1) The installed capital cost is the base system cost and does not include incentives or ESPC markup.

(2) Status Quo Life Cycle Cost (LCC) is the cost of purchasing electricity over 25-year period

(3) Sum of energy savings, incentive and RECs, and O&M cost for first year. Doesn't include debt payment.

Exhibit 2 Life Cycle Cost Analysis Results - Active Daylighting System

		Klystron Gallery
	Electricity Savings (MWh/yr)	704.4
	Installed Capital Cost (\$000) (1)	\$1,331
	2009 Electricity Cost (\$/kWh)	\$0.079
	Year 1 Energy Savings (\$000)	\$55.80
	25 Year Status Quo LCC (\$000) (2)	\$1,001.6
No Incentives		
	1st Yr Undiscounted Savings (\$000) (3)	\$66.96
ESPC (25 years)	System LCC (\$000)	\$1,336.9
	Simple Payback	21 years
PPA (25 years)	System LCC (\$000)	\$1,434.7
	Simple Payback	18 years

(1) The installed capital cost is the base system cost and does not include incentives or ESPC markup.

(2) Status Quo Life Cycle Cost (LCC) is the cost of purchasing electricity over 25-year period

(3) Sum of energy savings, and O&M savings for first year. Doesn't include debt payment.

Exhibit 3 Life Cycle Cost Analysis Results - Solar Thermal System

	Cafeteria Solar Hot Water (37° tilt) (1)	Cafeteria Solar Hot Water (90° tilt) (1)
Energy Savings (MMBtu/yr)	129	96
Installed Capital Cost (2)	\$24,000	\$24,000
Current Natural Gas Cost (\$/MMBtu)	\$7.33	\$7.33
Year 1 Energy Savings 1st Yr	\$1,182	\$880
Undiscounted Savings (3)	\$638	\$760
25 Year Status Quo LCC (4)	\$24,851	\$18,494
All Incentives		
System LCC	\$22,283	\$22,577
Simple Payback	16 years	21 years

- (1) The Cafeteria SHW systems are equivalent except for the mounting tilt angle to the roof (0° is horizontal, 90° is vertical).
- (2) The installed capital cost is the base system cost and does not include incentives or ESPC markup.
- (3) Sum of energy savings, incentives, and O&M cost for first year. Doesn't include debt payment.
- (4) Status Quo Life Cycle Cost (LCC) is the cost of purchasing natural gas over 25-year period.

SECTION 7
NEVADA TEST SITE

1. Introduction

The Nevada Test Site (NTS or Site) is located 65 miles northeast of Las Vegas, Nevada. NTS currently receives most of its power from the Nevada Power Company (NPC) under the utility's LGS-Transmission rate schedule. In addition to the NPC power, the Valley Electric Association (Valley or VEA), wheels approximately 2 MW of Western power to the Site under terms and conditions specified in a wheeling agreement between VEA and NTS. VEA interconnects with the government-owned NTS loop at the Jackass Flats Substation through a Valley-owned line running from its Pahrump Substation. NTS is interconnected with NPC at the Mercury Switching Center through a line from the Company's Northwest Substation. An NPC-owned line connects the Jackass Flats Substation to the Mercury Switching Center, establishing a Valley/NPC interconnection.

2. Projected Demands and Energy

Tables 7-1 and 7-2 show NTS' projected demand and energy for the next five years, from FY2009 through FY2013.

Table 7-1			
Nevada Test Site			
Demand Projections (kW)			
FY09-FY13			
Fiscal Year	Base Case Projected Demand	Cumulative Estimated Savings	Net Demand Requirements
2009	36,180	180	36,000
2010	59,180	180	59,000
2011	60,180	180	60,000
2012	60,180	180	60,000

Table 7-2 Nevada Test Site Energy Projections (mWh) FY09-FY13			
Fiscal Year	Base Case Energy Projections	Cumulative Estimated Savings	Net Energy Requirements
2009	207,151	1,598	205,553
2010	207,151	1,598	205,553
2011	336,075	1,598	335,377
2012	342,385	1,598	340,786
2013	342,384	1,598	340,786

In the 1997 Integrated Resource Plan (IRP), NTS set 5- and 10-year goals for electric power usage based on meeting the requirements of the Energy Power Act and Executive Order 12902. The Site has since amended its goals to meet the new requirements of Executive Order 13123, which was issued in June 1999. The goals now include reductions in the Site's total energy usage per square foot by 20 percent by FY 2005 and 25 percent by FY 2010, relative to a FY 1990 baseline. During FY 2001, National Security Technologies (NSTec) reported a 52.9 percent decrease in BTUs per square foot compared to FY 1985. This exceeds the 25 percent reduction goal set for FY 2010 by Executive Order 13123.

3. Current Demand-Side Programs

During the 1997-2003 period, NTS implemented several demand-side measures. These are summarized in Table 7-3.

TABLE 7-3

**Nevada Test Site
FY 1997 through 2003 Actual Project Summary Data**

<u>Project</u>	<u>Completion Date</u>	<u>Total Project Cost (\$000)</u>	<u>Annual Savings (mWh)</u>	<u>(\$000)</u>
HVAC Upgrades - Bldg. 23-725	Jul. 1997	184	810	47
Total FY 1997		\$184	810	\$47
Lighting Retrofit - Remote Sensing Lab	Sep. 1998	234	588	38
Total FY 1998		\$234	588	\$38
Power Metering Project	Aug. 1999	869	-	-
Photovoltaic Heat Trace System*	Sep. 1999	8	0.05	6
Total FY 1999		\$877	0.05	\$6
Programmable Thermostats ¹	May 2000	100	200	12
Total FY 2000		\$100	200	\$12
Total Energy Savings Projects Since FY 2001		\$1,395	1,598	\$103

* These are life-cycle costs, not just energy savings.

No new programs were implemented during 2005 and 2006.

4. Projected DSM/Energy Efficiency Projects

There currently are initiatives and projects being proposed to assist the NTS in meeting its future energy requirements using various energy conservation measures and new renewable resources. Some of these projects are briefly described below:

Proposed Renewable Resource Project- Concentrating Solar Power (CSP) Plant.

Solar electricity would be provided to the NTS by the building of a new Concentrating Solar Power (CSP) plant within the existing Solar Enterprise Zone at the NTS through Johnson Controls and partners. The use of this renewable energy would eliminate the purchase of a significant portion of NTS's most expensive on-peak utility power.

Johnson Controls would supply a 9 MW block of CSP electricity as a performance period service to NTS daily under an Energy Services Agreement.

Proposed Energy Conservation Measures (ECMs). A proposal for various ECMs is being developed for over 30 buildings located at the NTS. This proposal identifies implementation costs and potential energy and operational savings for these facilities. A preliminary list of these proposed ECMs are as follows:

- Boiler Replacement
- Building Controls Installation
- Pump Variable Frequency Drives (VFD) Installation
- Air side Economizer Installations
- Variable Air Volume (VAV) Retrofits
- Lighting Retrofits
- Lighting Controls
- Meter Installation
- Install Economizer Cycle
- Window Film

5. Energy Goals

NTS' long-term goals are designed to meet the requirements of Executive Order 13123. The goals now include reductions in the Site's total energy usage per square foot by 20 percent by FY 2005 and 25 percent by FY 2010, relative to a FY 1990 baseline. During FY 2001, National Security Technologies (NSTec) reported a 52.9 percent decrease in BTUs per square foot compared to FY 1985. This exceeds the 25 percent reduction goal set for FY 2010 by Executive Order 13123.

Since the time the 2004 IRP was prepared, there have been no changes to the previously reported projects and no new projects are planned for the Site. In all, the projects implemented from FY 1997 through FY 2004 are annually saving the Site 1,598 mWh and \$103,000. These are identified in Table 7-3.